WORK SCHEDULING GUIDE

Activity/Action		Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Roadway Shoulders	**R225**												
Repair Sod and/or Aggregate Shoulders & Approaches		■	■	■	■	■	■	■	■	■	■	■	■
Fly Coating						■	■	■	■	■			
Chip Seal							■	■	■	■	■		
Pothole Patching Asphalt & Partial Depth Concrete		■	■	■	■	■	■	■	■	■	■	■	■
Edge Ribbon							■	■	■	■	■		
Blade Patching					■	■	■	■	■	■	■		
Repair Concrete Shoulders & Approaches				■	■	■	■	■	■	■	■	■	
Roadway & Bridge Safety Features	**R227**												
Fences		■	■	■	■	■	■	■	■	■	■	■	■
Guardrails		■	■	■	■	■	■	■	■	■	■	■	■
Guard Cables		■	■	■	■	■	■	■	■	■	■	■	■
Impact Attenuator Devices		■	■	■	■	■	■	■	■	■	■	■	■
Traffic Barriers (Concrete) *A. Replacement*		■	■	■	■	■	■	■	■	■	■	■	■
Traffic Barriers (Concrete) *B. Repair*		■	■	■	■	■	■	■	■	■	■	■	■
Edge Rut Repair	**R22E**												
Edge Rut Repair (0.1 LM)		■	■	■	■	■	■	■	■	■	■	■	■
Patching Roads	**R311**												
Pothole Patching (Temporary/Emergency Repairs)		■	■	■	■	■	■	■	■	■	■	■	■
Pothole Patching (Temporary/Emergency Repairing BlowUps with Asphaltic Material)		■	■	■	■	■	■	■	■	■	■	■	■
Pothole Patching (Permanent partial depth repair on asphaltic or concrete pavements)				■	■	■	■	■	■	■	■	■	
Asphalt Pavement Repair	**R312**												
Box & Lay Down Machine Patching (TN)					■	■	■	■	■	■	■		
Blade, Box & Lay Down Machine Patching (TN)					■	■	■	■	■	■	■		
Concrete Replacement	**R313**												
Concrete Replacement - Full Depth (SY)				■	■	■	■	■	■	■	■	■	
Other Pavement Maintenance	**R314**												
Pavement Leveling (Mudjacking or Other Methods) (SY)					■	■	■	■	■	■	■	■	
Cold Milling (SY)		■	■	■	■	■	■	■	■	■	■	■	■
Pavement Preventative Maintenance	**R315**												
Fly Coating (LM)							■	■	■				
Crack & Joint Maintenance *A . Sealing Cracks, Joints & Edge Cracks*		■	■	■	■					■	■	■	■
Crack & Joint Maintenance *B. Milling High Joints*				■	■	■	■	■	■	■	■		
Drainage	**R316**												
Clean & Reshape Ditches *A. Earth Ditches*		■	■	■	■	■	■	■	■	■	■	■	■
Clean & Reshape Ditches *B. Paved Ditches*				■	■	■	■	■	■	■	■	■	
Repair Paved Ditches & Slopes					■	■	■	■	■	■	■	■	
Repair Curbing *A. Concrete Curbs*				■	■	■	■	■	■	■	■		
Repair Curbing *B. Asphalt Curbs*					■	■	■	■	■	■			
Repair Curbing *C. Drop Inlets & Storm Sewers*				■	■	■	■	■	■	■	■		
Channel Control		■	■	■	■	■	■	■	■	■	■	■	■
Slide Repair		■	■	■	■	■	■	■	■	■	■	■	■

WORK SCHEDULING GUIDE

Activity/Action		Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Pipe Culvert Repairs	**R319**												
Install Pipe Liners (LF)													
Clean & Repair Pipe & Box Culverts *A. Pipe Culverts*													
Clean & Repair Pipe & Box Culverts *B. Box Culverts*													
Replace Pipe & Box Culverts (LF)													
Sweeping	**R31B**												
Sweeping (LM)													
Chip Sealing	**R31C**												
Chip Sealing - Course Aggregate (LM)													
Chip Sealing - Fine Aggregate (LM)													
Scrub Seals (LM)													
Bridge Maintenance	**R321**												
Substructure Repairs *A. Sealing Abutment & Pier Caps*													
Substructure Repairs *B. Spot Painting of Bearings & Piling*													
Bridge Preventative Maintenance	**R322**												
Bridge Seal Coats (SY)													
Linseed Oil & In-Deck Seals (SY) *A. Linseed Oil*													
Linseed Oil & In-Deck Seals (SY) *B. In-Deck*													
Bridge Deck Repair	**R323**												
Deck Repair (SY) *A. Concrete*													
Deck Repair (SY) *B. Asphalt*													
Litter Pick-Up	**R411**												
Litter Pick-Up													
Landscaping	**R412**												
Landscaping													
Mowing	**R413**												
Mowing (AC)													
Brush Cutting & Tree Removal	**R414**												
Brush Cutting & Tree Removal													
Chemical Weed Control	**R415**												
Chemical Weed Control													