Three Year Engineering Factors, SFY 2016 Report:

Overhead Costs per Total Construction Costs

Report Key:

Projects are group by Work Type 1, and then work types are used to group projects into categories:

qry01MakeKey 11/15/2016

Category	Work Type	Projects completed in the time frame are tabulated and
MAJOR PROJECT	A- ADD LANES	categorized by primary work type and district. Excludes
MAJOR PROJECT	D- DUAL DIVIDED	payment projects, right of way only projects, and other
MAJOR PROJECT	F- FREEWAY	projects without actual construction costs.
MAJOR PROJECT	I- INTERCHANGE	
MAJOR PROJECT	M- MAJOR BRIDGE	Within each line item, all projects are totaled and then
MAJOR PROJECT	T- NEW OR IMPROVED 2 LANE	converted to percentages, based on the actual
		construction amount (actual CN). Not based on the
TCOS	1- ITS	actual total amount (actual Total). Thus, estimated
TCOS	2- ADA-TRANS	construction costs for a project can be used with
TCOS	B- BRIDGE REPLACEMENT	factors in this report to estimate overhead costs, which
TCOS	G- PREV MAINT-BRIDGE	add up to total costs.
TCOS	H- HIGH TYPE RESURFACING	
TCOS	J- PREV MAINT-PAVEMENT	PE% = (actual PE) / (actual CN)
TCOS	K- MED TYPE RESURFACING	CE% = (actual CE) / (actual CN)
TCOS	L- LOW TYPE RESURFACING	
TCOS	O- OTHER	RW acquisition = (actual land)
TCOS	P- PAVEMENT REPLACEMENT	RW incidentals = (total actual RW) - (actual land)
TCOS	Q- CMAQ	
TCOS	R- BRIDGE REHABILITATION	RWp% = (actual land) / (actual CN)
TCOS	S- BRDG RETROFIT AND STR	RWi% = (RW incidentals) / (actual CN)
TCOS	X- SAFETY	
TCOS	Y- ROUTINE MAINTENANCE	Total Engineering =
		((actual PE) + (actual CE) + (RW incidentals))
OTHER	E- ENHANCEMENTS	
OTHER	W- SHOULDER WIDENING	(actual CN)

Note: Only the first work type is used. For instance, many projects include shoulder widening, but few projects have shoulder widening as their first work type.

If a district has no completed projects of the work type, in the time frame, then the line item is removed from their table.

Note: Since SFY 2015's report, all projects are in the seven, reorganized districts. The group of "various"

districts has been removed.

Calculations:

Highlighted values:

n < 20 Each line item has an 'n' value indicating the number of projects included in the line. If the number of projects is low, then any unusual project can have a large effect on the results. Thus, lower 'n' values are highlighted and validity of the data should be confirmed.</p>

O% In some line items, none of the projects will include a type of engineering expense. For instance, Routine Maintenance normally does not include Right of Way Acquisition. The calculated rate will then be 0%, and these values have been highlighted.

7/1/2013 - 6/30/2016 Statewide Totals

Statewide						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
1- ITS	1.85%	18.28%	0.31%	20.43%	0.21%	3
2- ADA-TRANS	10.56%	28.55%	0.00%	39.11%	0.00%	8
A- ADD LANES	6.34%	2.53%	0.55%	9.42%	8.51%	28
B- BRIDGE REPLACEMENT	13.77%	10.07%	0.27%	24.11%	1.12%	70
D- DUAL DIVIDED	10.26%	5.98%	0.94%	17.18%	17.96%	13
E- ENHANCEMENTS	6.31%	12.84%	0.06%	19.20%	0.58%	25
F- FREEWAY	10.24%	5.77%	1.63%	17.64%	38.11%	18
G- PREV MAINT-BRIDGE	3.04%	6.06%	0.00%	9.10%	0.00%	23
H- HIGH TYPE RESURFACING	1.99%	6.43%	0.05%	8.46%	0.23%	60
I- INTERCHANGE	6.91%	7.11%	0.32%	14.34%	4.58%	39
J- PREV MAINT-PAVEMENT	2.62%	7.75%	0.03%	10.40%	0.04%	139
K- MED TYPE RESURFACING	1.37%	6.63%	0.00%	8.00%	0.00%	205
L- LOW TYPE RESURFACING	1.39%	6.23%	0.09%	7.71%	0.14%	132
M- MAJOR BRIDGE	14.38%	2.02%	1.17%	17.57%	6.14%	8
O- OTHER	7.98%	9.84%	0.41%	18.23%	2.08%	83
P- PAVEMENT REPLACEMENT	4.15%	6.70%	0.32%	11.16%	0.12%	11
Q- CMAQ	5.12%	10.02%	0.00%	15.14%	0.00%	29
R- BRIDGE REHABILITATION	5.90%	8.35%	0.03%	14.28%	0.06%	96
S- BRDG RETROFIT AND STR	385.83%	12.02%	5.13%	402.98%	164.31%	1
T- NEW OR IMPROVED 2 LANE	6.99%	8.76%	1.78%	17.53%	32.29%	8
W- SHOULDER WIDENING	6.36%	18.25%	0.71%	25.32%	1.13%	2
X- SAFETY	6.08%	10.05%	0.26%	16.39%	1.97%	115
Y- ROUTINE MAINTENANCE	1.64%	9.18%	0.00%	10.82%	0.02%	33
	7.03%	5.51%	0.50%	13.03%	6.58%	1,149
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=

	Premimary	Construction	Rigitt Of Way	TOtal	Rigill Of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	8.62%	3.95%	0.76%	13.32%	10.46%	114
TCOS	4.60%	7.77%	0.10%	12.47%	0.73%	1008
OTHER	6.31%	13.01%	0.08%	19.40%	0.59%	27
	7.03%	5.51%	0.50%	13.03%	6.58%	1,149

^{*} Only one project for Bridge Retrofit and Strengthening was completed during the current time frame. This one project was split into many smaller construction projects. Thus, all Preliminary Engineering is in the parent project, but most construction is in child projects, which were not included. Resulting in unusual percentage values.

7/1/2013 - 6/30/2016 by District

Northwest						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
B- BRIDGE REPLACEMENT	18.30%	7.59%	1.53%	27.43%	10.32%	6
G- PREV MAINT-BRIDGE	0.00%	4.43%	0.00%	4.43%	0.00%	1
H- HIGH TYPE RESURFACING	0.62%	5.25%	0.00%	5.86%	0.00%	8
J- PREV MAINT-PAVEMENT	0.65%	5.99%	0.00%	6.64%	0.00%	7
K- MED TYPE RESURFACING	1.09%	5.41%	0.00%	6.50%	0.00%	8
L- LOW TYPE RESURFACING	0.56%	4.11%	0.13%	4.80%	0.06%	45
M- MAJOR BRIDGE	1.03%	4.26%	0.00%	5.30%	0.00%	1
O- OTHER	8.15%	8.83%	1.03%	18.01%	2.23%	7
P- PAVEMENT REPLACEMENT	3.61%	9.34%	0.75%	13.70%	0.11%	4
R- BRIDGE REHABILITATION	4.38%	9.47%	0.07%	13.92%	0.05%	15
X- SAFETY	4.25%	7.44%	0.21%	11.90%	0.85%	7
	3.08%	6.14%	0.25%	9.48%	0.98%	109

	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	1.03%	4.26%	0.00%	5.30%	0.00%	1
TCOS	3.13%	6.18%	0.26%	9.57%	1.00%	108
	3.08%	6.14%	0.25%	9.48%	0.98%	109

7/1/2013 - 6/30/2016 by District

Northeast						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
A- ADD LANES	0.06%	14.15%	0.00%	14.21%	0.00%	2
B- BRIDGE REPLACEMENT	19.55%	13.38%	0.17%	33.10%	0.15%	12
D- DUAL DIVIDED	6.78%	8.50%	0.00%	15.28%	0.00%	2
E- ENHANCEMENTS	13.60%	26.02%	0.39%	40.02%	0.16%	3
G- PREV MAINT-BRIDGE	1.88%	14.99%	0.00%	16.87%	0.00%	7
H- HIGH TYPE RESURFACING	2.14%	6.18%	0.00%	8.32%	0.00%	5
I- INTERCHANGE	14.80%	10.79%	1.34%	26.93%	41.04%	1
J- PREV MAINT-PAVEMENT	0.87%	9.76%	0.00%	10.63%	0.00%	38
K- MED TYPE RESURFACING	3.24%	8.77%	0.00%	12.01%	0.00%	3
L- LOW TYPE RESURFACING	1.35%	8.31%	0.37%	10.02%	0.81%	24
O- OTHER	7.31%	10.73%	0.35%	18.40%	0.22%	6
P- PAVEMENT REPLACEMENT	0.00%	15.22%	0.00%	15.22%	0.00%	1
R- BRIDGE REHABILITATION	6.00%	11.32%	0.00%	17.32%	0.00%	23
X- SAFETY	12.67%	11.55%	0.77%	25.00%	10.27%	12
Y- ROUTINE MAINTENANCE	0.00%	42.24%	0.00%	42.24%	0.00%	4
	6.27%	10.08%	0.20%	16.55%	2.71%	143

	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	7.96%	9.33%	0.27%	17.56%	8.26%	5
TCOS	5.69%	10.06%	0.18%	15.94%	1.18%	135
OTHER	13.60%	26.02%	0.39%	40.02%	0.16%	3
	6.27%	10.08%	0.20%	16.55%	2.71%	143

7/1/2013 - 6/30/2016 by District

Kansas City						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
A- ADD LANES	5.60%	2.31%	0.44%	8.35%	4.05%	5
B- BRIDGE REPLACEMENT	13.54%	8.11%	0.00%	21.65%	0.04%	6
D- DUAL DIVIDED	10.01%	4.64%	1.46%	16.11%	7.75%	5
E- ENHANCEMENTS	6.64%	15.33%	0.00%	21.97%	0.00%	3
G- PREV MAINT-BRIDGE	3.83%	3.48%	0.00%	7.32%	0.00%	6
H- HIGH TYPE RESURFACING	3.66%	5.87%	0.00%	9.53%	0.00%	6
I- INTERCHANGE	6.89%	6.00%	0.31%	13.20%	4.61%	19
J- PREV MAINT-PAVEMENT	2.59%	7.97%	0.17%	10.73%	0.22%	14
K- MED TYPE RESURFACING	0.67%	8.00%	0.00%	8.68%	0.00%	19
L- LOW TYPE RESURFACING	1.60%	5.60%	0.04%	7.24%	0.00%	13
O- OTHER	9.24%	8.60%	0.36%	18.20%	1.43%	28
Q- CMAQ	0.84%	4.44%	0.00%	5.29%	0.00%	7
R- BRIDGE REHABILITATION	4.04%	6.39%	0.00%	10.43%	0.00%	14
T- NEW OR IMPROVED 2 LANE	9.26%	6.95%	1.42%	17.63%	37.55%	1
X- SAFETY	1.47%	8.78%	0.04%	10.30%	0.09%	16
Y- ROUTINE MAINTENANCE	0.03%	1.65%	0.00%	1.68%	0.00%	6
	5.77%	4.89%	0.38%	11.03%	3.70%	168

	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	6.65%	4.01%	0.53%	11.20%	5.37%	30
TCOS	3.89%	6.62%	0.07%	10.58%	0.24%	135
OTHER	6.64%	15.33%	0.00%	21.97%	0.00%	3
	5.77%	4.89%	0.38%	11.03%	3.70%	168

7/1/2013 - 6/30/2016 by District

Central						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
A- ADD LANES	8.20%	18.00%	3.87%	30.07%	19.82%	2
B- BRIDGE REPLACEMENT	18.44%	14.09%	0.27%	32.80%	0.62%	12
D- DUAL DIVIDED	10.84%	8.60%	0.00%	19.44%	0.00%	1
E- ENHANCEMENTS	5.63%	18.80%	0.29%	24.71%	0.43%	2
G- PREV MAINT-BRIDGE	3.09%	12.04%	0.00%	15.13%	0.00%	2
H- HIGH TYPE RESURFACING	0.73%	7.14%	0.00%	7.87%	0.00%	16
I- INTERCHANGE	4.73%	8.39%	0.00%	13.12%	0.00%	1
J- PREV MAINT-PAVEMENT	0.27%	7.05%	0.00%	7.33%	0.00%	23
K- MED TYPE RESURFACING	1.69%	7.92%	0.00%	9.60%	0.00%	23
L- LOW TYPE RESURFACING	0.54%	7.58%	0.00%	8.11%	0.00%	21
M- MAJOR BRIDGE	14.45%	4.21%	0.02%	18.68%	0.71%	1
O- OTHER	8.70%	11.54%	0.64%	20.87%	0.16%	7
P- PAVEMENT REPLACEMENT	6.09%	10.37%	0.14%	16.60%	0.38%	5
R- BRIDGE REHABILITATION	11.92%	10.69%	0.14%	22.76%	0.39%	12
X- SAFETY	4.48%	16.83%	0.16%	21.48%	2.48%	10
Y- ROUTINE MAINTENANCE	4.29%	18.23%	0.02%	22.53%	0.10%	8
	6.26%	8.67%	0.07%	15.00%	0.37%	146

	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	11.61%	6.36%	0.07%	18.04%	0.68%	5
TCOS	3.96%	9.51%	0.06%	13.53%	0.23%	139
OTHER	5.63%	18.80%	0.29%	24.71%	0.43%	2
	6.26%	8.67%	0.07%	15.00%	0.37%	146

7/1/2013 - 6/30/2016 by District

St. Louis						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
1- ITS	0.00%	0.00%	0.00%	0.00%	0.00%	1
A- ADD LANES	6.52%	1.27%	0.41%	8.20%	9.63%	4
B- BRIDGE REPLACEMENT	8.92%	8.65%	0.35%	17.91%	0.13%	6
D- DUAL DIVIDED	15.45%	6.22%	1.17%	22.84%	48.35%	2
E- ENHANCEMENTS	9.12%	15.15%	0.00%	24.27%	0.00%	3
F- FREEWAY	11.54%	5.07%	2.41%	19.02%	58.70%	3
G- PREV MAINT-BRIDGE	1.34%	6.90%	0.00%	8.24%	0.00%	7
H- HIGH TYPE RESURFACING	4.48%	8.92%	0.23%	13.63%	1.17%	14
I- INTERCHANGE	9.88%	8.16%	0.76%	18.80%	9.23%	2
J- PREV MAINT-PAVEMENT	3.96%	7.87%	0.00%	11.83%	0.00%	38
K- MED TYPE RESURFACING	5.80%	9.96%	0.00%	15.75%	0.00%	7
L- LOW TYPE RESURFACING	5.89%	17.30%	0.00%	23.19%	0.00%	1
M- MAJOR BRIDGE	14.64%	1.81%	1.30%	17.75%	6.79%	5
O- OTHER	9.57%	13.52%	0.57%	23.66%	1.99%	13
P- PAVEMENT REPLACEMENT	3.86%	2.41%	0.00%	6.26%	0.00%	1
Q- CMAQ	6.91%	12.45%	0.00%	19.36%	0.00%	21
R- BRIDGE REHABILITATION	4.55%	7.18%	0.00%	11.73%	0.00%	9
S- BRDG RETROFIT AND STR	385.83%	12.02%	5.13%	402.98%	164.31%	1
X- SAFETY	10.65%	12.39%	0.32%	23.36%	1.01%	21
Y- ROUTINE MAINTENANCE	0.00%	1.71%	0.00%	1.71%	0.00%	8
	10.15%	3.62%	0.78%	14.55%	11.98%	167
	D 1: :	Canatanatian	D: 1		Diabt of Man	

	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	10.39%	2.21%	0.92%	13.53%	14.45%	16
TCOS	9.19%	9.27%	0.17%	18.64%	1.96%	148
OTHER	9.12%	15.15%	0.00%	24.27%	0.00%	3
	10.15%	3.62%	0.78%	14.55%	11.98%	167

^{*} Only one project for Bridge Retrofit and Strengthening was completed during the current time frame. This one project was split into many smaller construction projects. Thus, all Preliminary Engineering is in the parent project, but most construction is in child projects, which were not included. Resulting in unusual percentage


7/1/2013 - 6/30/2016 by District


Southwest						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
1- ITS	2.55%	25.18%	0.42%	28.15%	0.28%	2
2- ADA-TRANS	10.56%	28.55%	0.00%	39.11%	0.00%	8
A- ADD LANES	8.91%	8.07%	1.02%	18.00%	12.76%	11
B- BRIDGE REPLACEMENT	10.08%	9.82%	0.00%	19.91%	0.00%	13
D- DUAL DIVIDED	3.08%	5.03%	0.00%	8.12%	0.00%	1
E- ENHANCEMENTS	9.45%	16.94%	0.00%	26.38%	0.00%	8
F- FREEWAY	7.90%	7.02%	0.23%	15.15%	1.04%	15
H- HIGH TYPE RESURFACING	0.69%	5.80%	0.00%	6.49%	0.00%	3
I- INTERCHANGE	6.69%	8.36%	0.28%	15.33%	2.82%	10
J- PREV MAINT-PAVEMENT	0.43%	7.54%	0.00%	7.97%	0.00%	11
K- MED TYPE RESURFACING	1.19%	6.10%	0.01%	7.29%	0.00%	112
L- LOW TYPE RESURFACING	2.89%	7.00%	0.00%	9.88%	0.00%	3
M- MAJOR BRIDGE	3.57%	1.49%	0.00%	5.06%	0.00%	1
O- OTHER	6.27%	14.66%	0.37%	21.29%	3.50%	13
Q- CMAQ	0.00%	1.63%	0.00%	1.63%	0.00%	1
R- BRIDGE REHABILITATION	4.96%	7.45%	0.00%	12.41%	0.00%	13
T- NEW OR IMPROVED 2 LANE	6.43%	9.61%	2.28%	18.31%	54.16%	3
X- SAFETY	7.36%	10.33%	0.31%	17.99%	1.87%	38
Y- ROUTINE MAINTENANCE	2.82%	12.75%	0.00%	15.57%	0.00%	2
	4.83%	7.61%	0.27%	12.72%	3.79%	268
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	7.03%	7.70%	0.56%	15.29%	8.12%	41
TCOS	2.99%	7.45%	0.04%	10.49%	0.30%	219
OTHER	9.45%	16.94%	0.00%	26.38%	0.00%	8
	4.83%	7.61%	0.27%	12.72%	3.79%	268


7/1/2013 - 6/30/2016 by District


Southeast						
	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Types	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
A- ADD LANES	6.21%	7.27%	1.65%	15.12%	16.52%	4
B- BRIDGE REPLACEMENT	13.50%	9.25%	0.16%	22.91%	0.24%	15
D- DUAL DIVIDED	6.50%	6.18%	1.12%	13.79%	12.97%	2
E- ENHANCEMENTS	3.23%	6.57%	0.01%	9.81%	1.25%	6
H- HIGH TYPE RESURFACING	0.39%	5.32%	0.00%	5.71%	0.00%	8
I- INTERCHANGE	3.73%	9.79%	0.00%	13.52%	0.00%	6
J- PREV MAINT-PAVEMENT	0.19%	3.49%	0.00%	3.68%	0.00%	8
K- MED TYPE RESURFACING	1.52%	6.31%	0.00%	7.83%	0.00%	33
L- LOW TYPE RESURFACING	2.14%	4.38%	0.00%	6.52%	0.00%	25
O- OTHER	4.08%	5.63%	0.04%	9.75%	3.46%	9
R- BRIDGE REHABILITATION	10.57%	13.00%	0.08%	23.64%	0.08%	10
T- NEW OR IMPROVED 2 LANE	6.13%	9.15%	1.61%	16.89%	13.04%	4
W- SHOULDER WIDENING	6.36%	18.25%	0.71%	25.32%	1.13%	2
X- SAFETY	2.33%	6.15%	0.18%	8.65%	1.54%	11
Y- ROUTINE MAINTENANCE	4.42%	18.93%	0.00%	23.35%	0.00%	5
	4.18%	7.01%	0.56%	11.76%	5.66%	148


	Preliminary	Construction	Right of Way	Total	Right of Way	
Work Type Categories	Engineering	Inspection	Incidentals	Engineering	Acquisition	n=
MAJOR PROJECT	5.86%	7.77%	1.29%	14.91%	12.70%	16
TCOS	2.95%	6.41%	0.04%	9.40%	0.56%	124
OTHER	3.46%	7.43%	0.06%	10.96%	1.25%	8
	4.18%	7.01%	0.56%	11.76%	5.66%	148






































































Three Year Engineering Factors, SFY 2016 Report Appendix: Comparison of Multi-Year Reports


The following compares Engineering Factors data for the last three reports. Each report includes the previous three years of data, so that each report includes some data overlapping previous reports. The 'year' indicated in each case is the year of the report. Thus, the "2016 Samples" are number of projects in State Fiscal Years 2014 to 2016. The purpose of this comparison is to check on consistency between multiple years. Projects are classified by work type and then grouped into three categories. These first graphs report on categories, and later graphs focus on work types.




The first graph shows statewide number of projects (samples sizes) in each year's report. A group with more samples (projects) is likely to produce better average values. For instance, the 'Other' category has about 25 samples per year. If one of them has unusual engineering costs, it will affect the group more than one out of a hundred or thousand samples in the other groups.




The second graph shows Preliminary Engineering (PE) per Construction (CN) has varied by about 2%, per report.




The third graph shows Construction Engineering (CE) per Construction (CN) has varied by about 2% per report, except the 'Other' category is up by about 3% with this year's report. In Total, CE has been 5% to 6% of CN in the last three reports.




Although there have been many changes over the years, we now have 8 Engineering Factor Reports. These show a trend for statewide CE / CN to be between 5% and 7%, with the average of all eight reports being 6.25%. SIMS uses a default CE value of 7% of CN.



This graphs shows the last three years of engineering factor data, statewide, per work type. Several of the work types have less than 20 projects in one or more reports. These work types are more likely to be affected by one unusual project, as opposed to types that have many samples. In particular, S- Bridge Retrofit and Strengthening has 1 to 3 projects per report, and one of the project in two of the reports is highly unusual. Thus, results for bridge retrofit and strengthening are not good predictors. Other low sample work types may have similar problems. Low sample work types have been highlighted in this and the following graphs.



This graph shows (per work type) percent factor of actual PE total divided by actual construction totals. In work types with large sample sizes, values changed between reports by less than +/- 2.3%



This graph shows (per work type) percent factor of actual CE total divided by actual construction totals. In work types with large sample sizes, values changed between reports by less than =/- 2.8%; except for Q – CMAQ projects, which had a change of about 4% per report.